

## Schedule - B

**Name Of Work: Construction of compound wall at Survey No: 173, Mirzapar, Bhuj**

It. No	Description	Unit	Qty	Rate	Amount
1	Excavation for foundation upto 1.5 m depth including sorting out and stacking of useful materials and disposing off the excavated stuff upto 50 Meter lead.(A) Loose or soft soil	Cumt	188.00		
2	Providing and laying cement concrete 1:4:8 (1-Cement : 4- coarse sand : 8- hand broken stone aggregates 40 mm nominal size) and curing complete excluding cost of formwork in (A) Foundation and Plinth (upto 10 ton)	Cumt	27.00		
3	Providing and laying controlled cement concrete M.200 and curing complete excluding the cost of formwork and reinforcement for reinforced concrete work in (A) Foundations, footings, Base of columns and Mass concrete (upto 10 ton)	Cumt	79.00		
4	Providing and laying controlled cement concrete M.200 and curing complete excluding the cost of formwork and reinforcement for reinforced concrete work in (C) Slabs,landing,shelves,Balconies Lintels, Beams, Girders and Cantilever upto floor two level. (upto 10 ton)	Cumt	28.00		
5	Providing and laying controlled cement concrete M.200 and curing complete excluding the cost of formwork and reinforcement for reinforced concrete work in (D) Columns, Pillars posts and struts upto floor two level. (upto 10 ton)	Cumt	17.00		
6	Coursed rubble masonry with hard stone of approved quality in superstructure above plinth level upto floor two level Cement Mortar 1:6 (1-Cement : 6-coarse sand) etc. complete. (upto 10 ton)	Cumt	157.00		
7	Providing and laying controlled cement concrete M.200 and curing complete excluding the cost of formwork and reinforcement for reinforced concrete work in (C) Slabs,landing,shelves,Balconies Lintels, Beams, Girders and Cantilever upto floor two level. (upto 10 ton)	Cumt	10.00		

8	Providing TMT Bar FE 415 reinforcement for R.C.C. work including bending, binding and placing in position complete upto floor two level (upto 10 ton)	KG	9760		
9	Providing and fixing M.S. grills of required pattern to wooden frames of windows etc. with M.S. flats at required spacings and frame around, square or round bars with round headed bolts and nuts or by screws. (B) ORNAMENTAL GRILL (upto 10 ton)	KG	5580.00		
10	Providing formwork of ordinary timber planking so as to give a rough finish including centering shuttering strutting and propping etc. Height of propping and centering below supporting floor to ceiling not exceeding 4 M. and removal of the same for in situ reinforced concrete and plain concrete work in. (A) Foundations Footings Bases of Columns etc. and Mass concrete. (upto 10 ton)	Sqmt	202.00		
11	Providing formwork of ordinary timber planking so as to give a rough finish including centering shuttering strutting and propping etc. height of propping and centering below supporting floor to ceiling not exceeding 4 M. and removal of the same for in situ reinforced concrete and plain concrete work in. (G) Columns Pillars Posts and struts. (1) Square Rectangular Polygonal in plan. (upto 10 ton)	Sqmt	223.00		
12	Providing formwork of ordinary timber planking so as to give a rough finish including centering shuttering strutting and propping etc. height of propping and centering below supporting floor to ceiling not exceeding 4 M. and removal of the same for in situ reinforced concrete and plain concrete work in. (H) (1) Sides and soffits of Beams Beam Haunchings cantilevers Girders Bressumers and Lintels not exceeding 1 M. in Depth. (upto 10 ton)	KG	248.00		

13	Providing and fixing 1mm thick M.S. sheet sliding shutters with frame and diagonal braces of 40 x 40 x 6 mm angle iron, 3.15 mm M.S. gusset plates at Junctions and corners 25 mm dia. pulley, 40 x 40 x 6mm angle and T-iron guide rail at top and bottom respectively with handles, stoppers and locking arrangement etc, including applying a priming coat of red lead paint. (upto 10 ton) including Painting two coats (excluding priming coat) on new steel and other metal surface with enamel paint, brushing, interior to give an even shade including cleaning the surface an even shade including clean the surface of all dirt, dust and other foreign matter	Sqmt	6.00		
14	Painting two coats (excluding priming coat) on new steel and other metal surface with enamel paint, brushing, interior to give an even shade including cleaning the surface an even shade including clean the surface of all dirt, dust and other foreign matter including Applying priming coat over new steel and other metal surface after and including preparing the surface by thoroughly cleaning, oil,grease, dirt and other foreign matter and scoured with brushes fine steel wood, scrapers and sand paper with ready mixed priming paint brushing red lead.	Sqmt	372.00		

Total Rs

